

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-091-19202-0000
 Spot: NENESW Sec 4 Twp 14 S Rng 22 E / W
2404 Feet from N / S Line of Section
3155 Feet from E / W Line of Section
 GPS: Lat: 38.861480 Long: 94.975470 Date: 3/28/11
 Lease Name: TANGLADE (HAMMER) Well #: HAMMER OW-1
 County: Johnson Total Vertical Depth: 600 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>PROD - Casing</u>	<u>2.000</u>	<u>600</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>PKR - Packer</u>	<u>1.000</u>	<u>450</u>	<u>450</u>	
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: GAS - Natural Gas - Production UIC Docket No.: _____ Date/Time to Plug: 5/10/11 / 9:00 am
 Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.
 Proposal Rcvd from: JIM KEPLEY Company Name: SAME Phone: (620) 431-2285


Proposed Plugging Report: **PLUG WELL WITH PORTLAND CEMENT FROM TD TO SURFACE.**
 KANSAS CORPORATION COMMISSION
JUL 01 2011 RECEIVED

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 5/10/11 / 3:00 pm KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
CLEAR AROUND LOCATION. SET 5 FT OF 12" SURFACE. PULL 100 FT OF 1". 1" BROKE OFF. FISH OUT REST OF 1". PUMP WATER DOWN 2" TO KILL GAS FLOW. RUN 1" INSIDE 2" TO 600 FT. WASH 1" DOWN OUTSIDE 2" TO 575 FT. PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE AND TOP OFF WELL. DIG DOWN AND CUT OFF WELL. EMPTY PIT AND BACKFILL. LEVEL AREA. PUMP TOTAL OF 163 SACKS OF PORTLAND CEMENT. WELL PLUGGED.				

Remarks: **CONTROL NUMBER 20110076-001. CONTRACT NUMBER 11782. REG. SEC. NAD 83**

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03

 (Technician)
 Form: District Plugging Report - _____