

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19348-00-01

Spot: SESWSW

Sec/Twnshp/Rge: 25-13S-15W

~~182~~ ~~80~~ feet from S Section Line, ~~451~~ ~~4620~~ feet from E Section Line

Lease Name: SELLENS (TWIN)

Well #: 2

County: RUSSELL

Total Vertical Depth: 3370 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	950		
PROD	5	3370		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/27/2012 12:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone:

Proposed
Plugging
Method:

Ordered 480sx 60/40 4% gel cement and 600# hulls.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/29/2012 4:15 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated @1600', 850', 420'
Ran tubing to 3350'.
Pumped 10sx gel followed by 75sx cmt w/100# hulls.
Pulled to 1660'. Pumped 175sx cmt w/200# hulls.
Pulled to 800'. Pumped 125 sx cmt. Cement circulated.
PTOH.
Pumped 40sx cmt down backside. 200 psi SIP.
Topped off w/25sx cmt. Cement falling back.
2/29/2012. Topped off w/40sx cmt.

Remarks: CONTROL #20120017-001 FEE FUND PROJECT SELLENS II WELL#2 TWIN

Plugged through: TBG

District: 04

Signed

Case Morris

(TECHNICIAN)

MAR 13 2012

RECEIVED

MAR 20 2012

KCC WICHITA

Form CP-2/3