


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 36 Twp. 17 Rge. 21W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Pickrell Drilling Company
Lease Name Casey Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 11, 1964
Application for plugging filed December 11, 1964
Application for plugging approved December 11, 1964
Plugging commenced December 11, 1964
Plugging completed December 11, 1964
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4245 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	341'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 540', set plug, cemented with 40 sacks.

Heavy mud to 240 feet, set plug, cemented with 20 sacks.

Heavy mud to 40 feet, set plug, cemented with 10 sacks.

Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS

(Signature of Owner or Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me, God.

(Signature) C. W. Sebits
C. W. Sebits
705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of December, 1964

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 4th National Bank Bldg
Wichita, Kansas

Rotary Drilling Commenced 11-30-64

Rotary Drilling Completed 12-10-64

LOCATION: CASEY No. 1, C SE NE Section 36-17-21W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (16 jts) 8 5/8" surface casing set at 341' cemented with 190 sacks cement. Circulated. Completed 5:30 P.M. November 30, 1964. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

285	Clay & Shale		<u>C. F. S.</u>
305	Sand		4100
341	Shale & Shells		4115
975	Shale, Red Rock		4125
1380	Shale & Shells		4135
1435	Anhydrite		4145
2100	Shale, Shells & Lime		4150
2535	Lime & Shale		4160
2690	Lime		4170
3505	Shale & Lime		4188
3877	Lime		4220
3980	Lime & Shale		4245
4115	Lime		
4150	Lime & Sand		<u>Slope Tests</u>
4160	Sand		2525
4182	Shale & Lime		3050
4245	Mississippian - RTE		3575
			4005
			<u>S. L. M.</u>
			3529
			3877
			4164

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1964

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 15th day of December, 1964, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966.

Maxine Blackman
Maxine Blackman, Notary Public