

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-23,081-00-00

LEASE NAME V. Higgins

WELL NUMBER 1

4290 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 6 TWP. 17S RGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed 2/6/87

Plugging Commenced 2/23/88

Plugging Completed 2/23/88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market, Suite 1000, Wichita, KS 67202

PHONE#(316) 267-4375 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #1, Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Cherokee Sd Depth to Top 4305' Bottom 4387' T.D. 4470'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee	oil	Surface	215'	8-5/8"	215'	none
		Surface	4470'	5 1/2"	4470'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
2 sacks hulls, 15 sacks 60/40 pozmix, 6% gel on bottom

at 1650' spot 20 sx 60/40 pozmix 6% gel

Pumped 120 sx ATL down 5 1/2" casing, 30 sx down annulus

Orders by Richard Lacey, Dan Goodrow on location during plugging.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. n/a

Address P.O. Box 31, Russell, KS 67665

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.

3-4-88
KAR - 4 1988

Galen B. Babcock

(Employee of Operator) or Cons. Operator or Division
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
 statements, and matters herein contained and the log of the above-described well as filed that
 the same are true and correct, so help me God.

(Signature) Galen Babcock

(Address) 125 N. Market #1000 Wichita Ks 67202

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 88

Glenna E. Lowe
 Notary Public

My Commission Expires: 9-18-91

