

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15135-19077-00-00

LEASE NAME Ummel AB

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line
NE NW

SEC. 11 TWP. 17 SRGE. 24W(E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 8-7-87

Plugging Completed 8-17-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

Rt. 3 Box 20-A

ADDRESS Great Bend, Kansas 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4485'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	228'	none
				5-1/2"	4474'	2058'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4420' and 5 sacks cement. Shot pipe @2645', 2456', 2239', 2058', pulled a total of 63 joints of 5-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 150 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 19th day of August, 19 87

Irene Hoover
Notary Public

My Commission Expires:



8.21.87
AUG 21 1987 Form CP-4
Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas



Mike Hayden	Governor
Keith R. Henley	Chairman
Rich Kowalewski	Commissioner
Margalee Wright	Commissioner
Judith A. McConnell	Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 200 Colorado Derby Building
 202 West 1st Street
 WICHITA, KANSAS 67202-1286

THIS NOTICE

AUG 11 '87

EXPIRES

May 11, 1987

WELL PLUGGING NOTICE

Ummel "AB" #2
 NE/4 NW/4
 Sec. 11-17-22W
 Ness County

Phillips Petroleum Company
 Route 3, Box 20-A
 Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
 Acting Director
 State Corporation Commission

Please contact the district office to review your suggested method of plugging
 DIST. #1 302 West McArtor, Dodge City, KS 67801 (316) 225-6760
 five days prior to plugging the well (KAR-82-3-113).