

CASE NAME Pfaff

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
3300 Ft. from S Section Lin.

660 Ft. from E Section Lin.

SEC. 11 TWP. 17S RGE. 22 (X) or (W)

COUNTY Ness

LEASE OPERATOR Sunflower Exploration

ADDRESS Route 1, Box 5 Brownell, Kansas 67521

PHONE (913) 481-2286 OPERATORS LICENSE NO. 30336

Character of Well D&A

Date Well Completed 9/20/96

Plugging Commenced 1:30AM 9/20/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4:00AM 9/20/96

The plugging proposal was approved on 9/19/96 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation None Depth to Top Bottom T.O. 4422

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	213	8 5/8	213.94	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s

1st Plug @ 1705' w/50sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes with 48 Vis. Mud

2nd Plug @ 920' w/80sks 15sks In Rat Hole Plugs displaced with mud.

3rd Plug @ 240' w/40sks 205sks 60/40Poz 6%Gel w/1#FS/sk By Allied Cementing

4th Plug @ 40' w/10sks Completed @ 4:00AM 9/20/96

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601-0763


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Sunflower Exploration

STATE OF KANSAS COUNTY OF ELLIS, ss.

Ron Nelson (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed i the same are true and correct, so help me God.

(Signature) Ron Nelson

(Address) 215 E. 5th Hays, Ks. 67601



AND SWORN TO before me this 20th day of November, 1996

[Signature] Notary Public

My Commission Expires: 1-10-99

USE ONLY ONE SIDE OF EACH FORM



Discovery Drilling

P.O. Box 763 • Hays, KS 67601 • OFFICE (913) 623-2920 • CELLULAR (913) 635-1511

ORIGINAL

DRILLERS LOG

15-135-23950-00-00

Operator: **SUNFLOWER EXPLORATION #30336**
Route 1, Box 5
Brownell, KS 67521

Contractor: **DISCOVERY DRILLING, Inc.**
P.O. Box 763
Hays, KS 67601

Lease: Pfaff #1

Location: C SE/NE
Sec. 11/17S/22W
Ness Co., KS

Loggers Total Depth: 4422'

Rotary Total Depth: 4422'

Commenced: 9/13/96

Casing: 8 5/8 @ 213.94 w/150 sks.

Elevation: 2387' Gr./2395 KB

Completed: 9/20/96

Status: D&A

RECEIVED
KANSAS CORP COM
1996 NOV 22 12:06

DEPTHS & FORMATIONS

(All Measurements from K.B.)

Surface, Sand & Shales	0'	Shales	1705'
Dakota Sand	666'	Shales & Lime	1863'
Shales	865'	Shales	2098'
Cedar Hill Sand	1104'	Shales & Lime	2348'
Red Bed Shale	1362'	Lime & Shale	3781'
Anhydrite	1670'	RTD	4422'
Base Anhydrite	1705'		

STATE OF KANSAS)
) SS
COUNTY OF ELLIS)


I, Thomas H. Alm, of Discovery Drilling, Inc. state that to the best of my knowledge the above and foregoing is a true and correct log of the above captioned well.

Thomas H. Alm

Thomas H. Alm

Subscribed and sworn to before me on: 9-23-96.

My Commission Expires: 10-12-98



Christine Schlyer

Notary Public

(Place stamp or seal above)