


15-135-21325-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 16 Twp. 17S Rge. (E) 25 (W)
Location as "NE/CNWKSW" or footage from lines Approx. NE SE
Lease Owner Chief Drilling Co., Inc.
Lease Name Ryan Well No. 1
Office Address 905 Century Plaza, Wichita, Ka. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-12-77 19
Application for plugging filed 5-16-77 19
Application for plugging approved 5-12-77 19
Plugging commenced 5-12-77 19
Plugging completed 5-12-77 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4448 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	290'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 700' w/70 sx. cement
Plugged through drill pipe @ 240' w/20 sx. cement
Plugged through drill pipe @ 40' w/10 sx. cement

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1977
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Jim Robinson*
905 Century Plaza, Wichita, Ka. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of May, 1977

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard
Notary Public.

My commission expires _____

WELL LOG

15-135-21325-00-00

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 RYAN
Approx. NE SE
Sec. 16-17S-25W
Ness County, Kansas
COMMENCED: April 5, 1977
COMPLETED: April 12, 1977

CONTRACTOR: Company Tools
CASING RECORD: 8 5/8" @ 290' w/165 sx.

FORMATION	FROM	TO
Surface Sand	0	295
Sand & Shale	295	2545
Shale	2545	3156
Shale & Sand	3156	3307
Shale	3307	4365
Lime & Shale	4365	4432
Lime	4432	4448
RTD	4448	

ELEVATIONS

2472 Gr.
2474 D.F.
2477 K.B.

FORMATION TOPS

Heebner	3811 - 1334
Lansing	3853 - 1376
BKC	4150 - 1673
Ft. Scott	4356 - 1879
RTD	4448 - 1971

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1977
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the Approx. NE SE of Section 16, 17S-25W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 16th day of May, 1977.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard, Notary Public