

15-135-20003-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 35 Twp. 16 Rge. (E) 24 (W)

Location as "NE/CNW/SW" or footage from lines. SW SW
Lease Owner Beardmore Oil Inc.
Lease Name Horchem Well No. 1
Office Address Suite 700 - One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil 67202
Date well completed 19
Application for plugging filed Dec. 14 19 71
Application for plugging approved 19
Plugging commenced Jan. 8 19 72
Plugging completed Jan. 19 19 72
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4507 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-------|--------|--------|----------------------------------|
| | | 0 | 202' | 8 5/8" | 202' | none |
| | | 0 | 4494' | 5 1/2" | 4494' | 1615.20 plastic 1124.77 plain |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 4450' and dumped 5 sacks of cement.
Plugged well pumping in 3 sacks of hulls, 25 sacks of mud and 120 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1972
CONSERVATION DIVISION
Wichita, Kansas
01-27-1972

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 72

My commission expires Feb. 10, 1975

George A. Meyer
Notary Public

15-135-20003-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1971

CONSERVATION DIVISION
Wichita, Kansas

12-15-1971

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG

HORCHEM #1

LOCATED: SW SW Section 35-16S-24W, Ness County, Kansas

OWNER: Beardmore Drilling Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 12, 1967

COMPLETED: January 23, 1967

ROTARY TOTAL DEPTH: 4507'

LOG

CASING RECORD

| | |
|-------------|--------------------|
| 0 - 216 | Sand, Clay & Shale |
| 216 - 1838 | Shale & Sand |
| 1838 - 1845 | Anhydrite |
| 1845 - 1960 | Anhydrite & Shale |
| 1960 - 3030 | Lime & Shale |
| 3030 - 3263 | Shale |
| 3263 - 3975 | Shale & Lime |
| 3975 - 4507 | Lime T.D. |

Run 10 joints (202') 8-5/8" casing, pipe set at 214' K.B. with 175 sacks common cement. Plug was down at 1:30 a.m..

Run 145 joints 5-1/2" 15.5# seamless casing, 4524' pipe set at 4494' K.B., cemented with 100 sacks regular cement. Plug was down at 7:00 p.m. 1-23-67 by Globe.