


15-135-21407-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 33 Twp. 16 Rge. 24 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
SW SW
Lease Owner Pickereell Drilling Company
Lease Name Side Bottom B#1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/2/78 _____ 19____
Plugging completed 2/17/78 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____
If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4509
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	215	none
				4 $\frac{1}{2}$ "	4488'	3041'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded from 4509 to 4450' and dumped 3 sacks cement. Shot pipe at 3431' and worked pipe.
Shot again at 3431', 3330', 3230', 3025', pulled 90 joints. Pumped 20 sacks gel, 70 sacks
cement, 10 sacks gel. Released plug and pumped 70 sacks cement.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of Feb., 19 78

Margaret Melcher
Notary Public.

My commission expires
RECEIVED
STATE CORPORATION COMMISSION



FEB 27 1978
02-27-1978
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
205 LITWIN BLDG.
WICHITA, KS. 67202
LOCATION: SIDEBOTTOM "B" #1
SW SW Sec. 33-16S-24W
NESS COUNTY, KANSAS
CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

Rotary Drilling Commenced 12-30-77
Rotary Drilling Completed 1-07-78

CASING RECORD: 8 5/8" surface csg. set at 215' with 150sx.
4 1/2" prod csg. set at 4488' w/200sx.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Top Soil & Clay	20
Shale	217
Shale	1211
Blaine	1219
Shale	1410
Sand & Shale	1824
Sand & Shale	1835
Shale	1864
Shale	2190
Shale & Lime	2489
Lime & Shale	2610
Shale & Lime	2820
Lime & Shale	2970
Shale & Lime	3165
Lime & Shale	3320
Lime & Shale	3495
Shale & Lime	3690
Lime	3880
Lime	4020
Lime & Shale	4135
Lime	4235
Lime	4335
Lime	4390
Lime & Sand	4470
Lime	4490

RECEIVED
STATE CORPORATION COMMISSION

FEB 03 1978
02-03-1978
CONSERVATION DIV. S.O.W.
Wichita, Kansas

The undersigned, Jack Gurley, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By Jack Gurley
Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 2 day of February, 19 78, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared Jack Gurley

, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: _____

Jo Ann Sarver
Notary Public

Jo Ann Sarver



15-135-21407-00-00

OPERATOR: PICKRELL DRILLING COMPANY
WELL: SIDEBOTTOM "B" #1
LOC.: SW SW Sec. 33-16S-24W, Ness City, Ks.
T.D. 4509 (Cable Tool)
CASING:
SURFACE: 8 5/8" @ 215' w/150sx. common
LONG STRING: 4 1/2" 10.5# K-55 @ 4488 w/150sx. 50-50
Poz w/4% gel plus 50 sx. common.
OPEN HOLE: 4488-4509
TOP OF CEMENT: 3208 (Theoretical)
3440 (Estimated, based on 82% fillup)

ST. RECEIVED
STANDARD OIL COMPANY

FEB 03 1978

02-03-1978
STANDARD OIL COMPANY
Wichita, Kansas