

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,821-00-00

LEASE NAME Sidebottom

WELL NUMBER 2-33

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 33 TWP. 16 RGE. 24 (S or W)

COUNTY Pratt

Date Well Completed 5-24-85

Plugging Commenced 5-24-85

Plugging Completed 5-24-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P. O. Box 947, Pratt, Kansas 67124

PHONE# (316) 672-7581 OPERATORS LICENSE NO. 5087

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	306	8 5/8"	5-17-85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged well with 175 sxs 60/40 poz, 2% gel, 3% cc as follows: 1860'-50 sxs; 930'-50 sxs; 340'-50 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs. Job by Halliburton. Plug down at 6:30 p.m. on May 24, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. _____

Address P. O. Box 329, Pratt, Kansas 67124


STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little (Employee of Operator) of _____

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 30th day of May, 19 85

Mary L. Tjaden
Notary Public

My Commission Expires: 3/22/88



Oilfield Services, Inc.

15-135-22821-00-00

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Sidebottom #2-33
 NE SE SW Sec. 33-16S-24W
 Ness County, Kansas
 Commenced: 5-17-85
 Completed: 5-24-85
 API #15-135-22,821
 Operator: Texas Energies, Inc.

Depth		Formation	Remarks
From	To		
0	314	Clay, Sand, Shale	Ran 7 joints (296') new, 24#, 8 5/8" surface casing. Set at 306' with 190 sxs Common, 2% gel, 3%cc. Job by Halliburton. Cement did circulate. Plug down at 8 p.m. on May 17, 1985.
314	928	Sand, Shale	
928	1871	Clay, Sand, Shale	
1871	4550	Lime, Shale	
		T.D.	

RTD 4550'

Plugged well with 175 sxs 60/40 poz, 2% gel, 3% cc as follows: 1860'-50 sxs; 930'-50 sxs; 340'-50 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs. Job by Halliburton. Plug down at 6:30 p.m. on May 24, 1985. State Plugger was out of the Dodge City, Kansas office.


STATE OF KANSAS)
)
 COUNTY OF PRATT) ss

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

Arnie Little

 ARNIE LITTLE, VICE-PRESIDENT



RECEIVED
 STATE CORPORATION COMMISSION

Mary L. Tjaden

 NOTARY PUBLIC

MAY 31 1985

My Commission Expires:

3/22/88

CONSERVATION DIVISION
 Wichita, Kansas

05-31-1985