

15-135-20046-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 33 Twp. 16S Rge. 24 (E) W (W)
Location as "NE/CNW*SW*" or footage from lines C NE NE

Lease Owner Mull Drilling Company

Lease Name Miller Well No. 1

Office Address 1625 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7/28/ 1967

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 7/28 1967

Plugging completed 7/28 1967

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 4532 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface hole	water	surface	296'	8 5/8"		left in
(see attached log)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 90 sacks cement to 870'. Set plug @ 280' and pump
25 sacks cement. Heavy mud to 40'. Plug & bridge at
40'. Cement to cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1967
08-01-1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Donelson Drilling Company

Address 619 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

James L. Donelson (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson

619 First National Bank Building

(Address)

Subscribed and sworn to before me this 31st day of July, 1967

Carolyn L. Scott
Notary Public.



My commission expires April 16, 1969

15-135-20046-00-00

#1 MILLER

Mull Drilling Company

Total Depth: 4532'

Elevation: 2528 GL, 2533 KB

Contractor: Donelson Drilling Co.

Location: C NE NE, Sec. 33-16S-24W

Commenced: 7/17/67

Ness County, Kansas

Completed: 7/28/67

Casing Record: 289.93' 8 5/8"
set @ 296' w/ 190 sks. cmt.

Formation:

Depth:

Surface Hole

296'

Shale & Sand

1190'

Shale

1330'

Sand

1480'

Shale & Lime

1723'

Sand & Shale

1875'

Shale

2100'

Shale & Salt

2320'

Shale & Lime

2780'

Lime & Shale stks.

2903'

Lime

3030'

Lime & Shale

3905'

Lime

4532' TD


AUG 1 1967
08-01-1967
COUNTY CLERK
NESS COUNTY, KANSAS

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

DONELSON DRILLING COMPANY

James L. Donelson
James L. Donelson

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)



Subscribed and sworn to before me, a Notary Public in and for said county and state, this 31st day of July, 1967.

My Commission expires: April 16, 1969.

Carolyn L. Scott
Carolyn L. Scott