

15-135-20254-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1969

CONSERVATION DIVISION
Wichita, Kansas

06-02-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Co.

Complete Address: 520 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name Wagner Well No. 1

Location C SE NE Sec. 28 Twp. 17 Rge. (E) (W) 21

County Ness Total Depth 4295

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Hellar Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 12:30P Day 29 Month 5 Year 1969

The Above well was plugged as follows:

RTD 4295' 8 5/8 csg set at 413' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 50 sk cmt

thru drill pipe. Heavy mud to 390' set cementing plug and displaced 25 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6/3/69
INV. NO. 9848-W