

15-135-20572-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company

Complete Address 435 Page Court 220 W. Douglas Wichita, Kansas

Lease Name Wagner Well No. 1

Location NE NW SE Sec. 28 Twp. 17 Rge. (E) (W) 21

County Ness Total Depth 4260'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 11:15A Day 23 Month 2 Year 1972

The above well was plugged as follows:

RTD 4260' 8 5/8 csg set at 275' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of celliaz.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/28/72

INV. NO. 5243-W

Signed: [Signature]
Well Plugging Supervisor