

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Petroleum Management, Inc.

Complete Address Box 922 Great Bend, Kansas 67530

Lease Name Gleve Well No. 1

Location C NW Sec. 5 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 3651

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 11A Day 13 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 3651' 8 5/8 csg set at 203' cwc

5 1/2 csg set at 3678' cw 100 sk cmt.

5 1/2 csg PSTD 3651' packer at 3325 Perf at (3076-3086)

Pumped 15 sk cmt plug leaving top of plug (3050)

Cutoff and recovered 780' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/5 sk hulls, 70 sk 50-50 poz cmt 6%,

5 sk gel, plug and 60 sk 50-50 poz cmt 6%.

Cmt (0-250) Gel (250-650) Cmt (650-950) Gel. (950-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/16/69

INV. NO. 475-W

Signed: Geo F. Messing
Well Plugging Supervisor