

15-135-20857-00.00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 8 - 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Co.

Complete Address Box 287, Great Bend, Kansas 67530

Lease Name Mollenkamp Well No. 1-AB

CSE SW

Location 1980' FWL & 660' FSL of SW/4 Sec. 4 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4510'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Slawson Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11:40 P Day 4 Month 4 Year 1974

The above well was plugged as follows:

RTD 4510' 8 5/8 csg set at 307' cwc.

Gunned pits, circulated heavy mud, set 75 sk cem. plug (4502'-4302')

Filled hole with heavy mud to 1180' -set 50 sk cem. plug (1180'-1030')

Filled hole with heavy mud to 357' -set 50 sk cem. plug (357'-257')

Filled hole with heavy mud to 40' set cementing plug, 1/4 sk hulls and 10 sk cem.
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo A. Massey
Well Plugging Supervisor

INVOICED

DATE 4/9/74

INV. NO. 8909-W