

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling Inc.

Complete Address Box 18407 Wichita, Kansas

Lease Name Breit Well No. 1

Location NE NE Sec. 2 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4510'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30 P Day 4 Month 1 Year 1974

The above well was plugged as follows:

RTD 4510' 8 5/8 csg set at 284' ewl 180 sk. Cmt. Mat. 50-50 pez W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1/9/74
INV. NO. 8385-W