

15-101-30000-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morrison-Producing-Company,

Complete Address: Box # 712, Eldorado, Kansas.

Lease Name Evel Well No. 1

Location CSE-SE Sec. 12 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4535'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 3:00PM Day 3 Month 6 Year 1965

The Above well was plugged as follows:

102'--8 5/8" Surface pipe, cement circulated with 125 Sx.
4534'--5 1/2" Production casing cemented with 125 Sx. Well plugged back to 4264'. Top perforations @ 3948'.

Sanded well back to 3935' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" to 560' and circulated heavy gel mud. (Used 25 Sx.). Pulled 5 1/2" to 475' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 200' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 6/11/65
INV. NO. 1299-w