

15-101-20032-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson, Incorporated.

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name USA Well No. 2

Location W/2-NE-NW Sec. 12 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 1520'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated.

Address 408 One-Twenty Building, Wichita, Kansas License No.

Operation Completed: Hour 3:00 AM Day 27 Month 2 Year 1972

The above well was plugged as follows:

Circulated hole with heavy mud. Pulled DP to 4483' and displaced 40 Sx. cement thru
DP from 4483' to 4357'. Pulled DP to 875' and displaced 110 Cu. Ft. cement thru DP
from 875' to 550'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 3/1/72
INV. NO. 5248-W