

15-101-20030-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Offner Well No. A-1

Location SE-SW-NE Sec. 2 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4470'.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Slawson Drilling, Incorporated,

Address 408 One-Twenty Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 6:45 AM Day 7 Month 2 Year 1972

The above well was plugged as follows:

236'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 600'.

Circulated hole with heavy mud. Pulled DP to 825' and displaced 110 Cu. Ft. cement
thru DP from 825' to 500'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement from 40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. B. Nichols
Well Plugging Supervisor

DATE 2/14/72
INV. NO. 5169-W