

15-159-20334-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Robert D. Holliday

Complete Address 38 Walnut Plaza, Great Bend, Kansas 67530

Lease Name Wellman Ranch Well No. 1

Location C E/2 SW SW Sec. 28 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 3601'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Woodman & Iannitti Drilling Company

Address 706 Union Nat'l Bldg., Wichita, Kansas License No.       

Operation Completed: Hour 3:15 PM Day 13 Month October Year 1970

The above well was plugged as follows:

Hole filled with mud to 200'. Plug and 1/4 sack hulls pushed to 200' and hole cemented with 25 sacks cement through drill pipe. Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole bridged and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: William J. Somers  
Well Plugging Supervisor

DATE 10-16-70

INV. NO. 2690-W