

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1966
12-20-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Jay-Bee Oil Company

Complete Address: 515 Union Center, Wichita, Kansas

Lease Name Wellman Well No. 1

Location NW NE NW Sec. 28 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 3575'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Graves Drilling Co., Inc.

Address: 412 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour 10:30 AM Day 16 Month December Year 1966

The Above well was plugged as follows:

65 sacks cement pumped through drill pipe (3400' to 3300'). Hole filled with mud to
260'. Plug and 1/4 sack hulls pushed to 260' and hole cemented with 25 sacks rumped
through drill pipe. Hole filled with mud to 60'. Plug and 1/2 sack hulls pushed to
60' and hole cemented to base of cellar with 20 sacks. Rathole bridged, and cemented
with 2 sacks. (Cities Service Gas Co. underground storage area) Haliburton Cementing
Co. pumped cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12/20/66
INV. NO. 4492-U