



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 11 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Estel Fox of Morrison Producing Co., has this date requested permission to plug the following described well:

Mr. Fox guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing Company,

Complete Address: Box #712, Eldorado, Kansas.

Lease Name: Evel Well No. 1

Location: CSE-SE Sec. 12 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4535 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Fox was instructed to plug the well as follows:

102'--3 5/8" Surface pipe, cement circulated with 125 Sx.
4534'--5 1/2" Production casing cemented with 125 Sx. Top of
cement @ 3700'. Well plugged back to 3978'. Top perforations
@ 3948'.
Sand well back to 3935' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 120' and dis-
place 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 10
Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent