



15-159-30197-0890

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED November 18, 1965
STATE CORPORATION COMMISSION

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

NOV 24 1965

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Earl Rowe of Slawson Drilling Co. has this
date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Kansas

Lease Name: Smith "G" Well No. 1

Location: SW SE NE Sec. 10 Twp. 21 Rge. 9 (~~S~~) (W) X

County Rice Total Depth 2984' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole


Mr. Rowe was instructed to plug the well as follows:

Fill hole with mud to 235'. Push plug and 1/4 sack hulls to
235' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent