



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1959
CONSERVATION DIVISION
WICHITA, KANSAS

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date April 2, 19 59, authorized the following plugging operation:

Operator's Full Name: Lee Phillips Oil Co.

Complete Address: 1402 Union Natl. Bldg., Wichita, Kansas

Lease Name: Read Well No. 1

Location: SE-NW-NW Sec. 11 Twp. 21 Rge. 9 (E) (W) X

County: Rice Total Depth: 337 1/4

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole with heavy mud to 280'
Push plug and 1/4 sack hulls to 280' and cement with 20 sacks thru
drill pipe. Fill hole to 40' with heavy mud--push plug and 1/4 sacks
hulls to 40'--cement with 10 sacks. Fill, bridge, and cement
rathole with 2 sacks.

Very truly yours,

Signed: Albert J. Lovin
Conservation Division Agent