



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

October 13, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Flake of Woodman-Iannitti Drlg., Co. has this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Robert D. Holliday

Complete Address: 38 Walnut Plaza, Great Bend, Kansas 67530

Lease Name: Wellman Ranch Well No. 1

Location: C E/2 SW SW Sec. 28 Twp. 21 Rge. 9 ~~(E)~~ (W) X

County: Rice Total Depth 3601' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Flake was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and  
cement hole with 25 sacks cement through drill pipe. Fill hole with  
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10  
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent