

State of Kansas



15-159-30306-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 16, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1966

12-20-66
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Robert Miller of Graves Drilling Co., Inc. has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Jay-Bee Oil Company

Complete Address: 515 Union Center, Wichita, Kansas

Lease Name: Wellman Well No. 1

Location: NW NE NW Sec. 28 Twp. 21 Rge. 9 (E)(W) X

County Rice Total Depth 3575' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

Hole to be cemented from 3400' to 3300' with 65 sacks cement pumped through drill pipe. (Cities Service Gas Co. underground storage area.)

Fill hole with mud to 260'. Push plug and 1/4 sack hulls to 260' and cement hole with 25 sacks through drill pipe. Fill hole with mud to

60'. Push plug and 1/2 sack hulls to 60' and cap hole with 20 sacks

cement. Bridge rathole, and cement Very truly yours,
with 2 sacks.

Arthur J. Leonard
Conservation Division Agent