

15-159-20008-0050

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 13, 1967  
**RECEIVED**  
STATE CORPORATION COMMISSION  
FEB 20 1967  
CONSERVATION DIVISION  
Wichita, Kansas  
02-20-67

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: <sup>KEEN</sup> Keen Drilling Co., Inc.

Complete Address: 337 Union Center, Wichita, Kansas

Lease Name: Plush Well No. 1

Location: C NE NW Sec. 34 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 3530' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Musgrove was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/4 sack hulls to 240' and  
cement hole with 25 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Albert J. Roman  
Conservation Division Agent