

State of Kansas



FORM CP-2

15-077-20309-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Hana of Anadarko Prod. Co has this

date requested permission to plug the following described well:

Mr. Hana guarantees payment of the plugging fee.

Operator's full Name: Anadarko Prod. Co

Complete Address: Box 351 Liberal, KS

Lease Name: Shelton A Well No. 1

Location: SE/SW Sec. 10 Twp. 33 Rge. 7 (E)(W) W

County: Harper Total Depth 4583 Oil Well     

Gas Well      Input Well      SWD Well      D & A      X Lost Hole     

Mr. Hanna was instructed to plug the well as follows:

326 ft 8 5/8 surface cemented with 300 sacks. 4586 ft

4 1/2 long string cemented with 125 sacks. Open hole. Pump

50 sacks cement to 4300 ft. pulled 3600 ft 4 1/2. Pump plug,

50 sacks cement to 350 ft. Mud to 40 ft, plug, 1/2 sack

balls, 10 sacks cement to surface.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,