

State of Kansas



15-135-20046-00-00

FORM - CP-2
Rev. 9-8-64

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1967
07-31-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Berenz of Donelson Drlg. has this
date requested permission to plug the following described well:

Mr. Berenz guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Co. Inc.,

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name: Miller Well No. 1

Location: C NE NE Sec. 33 Twp. 16 Rge. 24 (E)(W) X

County Ness Total Depth 4532 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Berenz was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 870' and displace
90 sc cement thru drill pipe. Heavy mud to 280' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug. 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent