

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 29 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Haynes Oil Company 15051-02579-00-00

Complete Address: Box 329 Russell, Kansas 67665

Lease Name Froelich "A" Well No. 4

Location SW SW SW Sec. 3 Twp. 13 Rge. (E) (W) 16

County Ellis Total Depth 3461

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3P Day 26 Month 7 Year 1969

The Above well was plugged as follows:

Total Depth 3461' 8 5/8 csg set at 200' cwc

4 1/2 csg set at 3460' with top perf. (3233)

Filled 4 1/2-csg W/sd. (3200-3461) Dumped 4-sk cmt W/dump bailer. (3160-3200)

Cutoff and recovered 2735' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/4 sk hulls, plug and 100 sk 50-50 poz
cmt. W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/29/69

INV. NO. 191-W

Signed: Leo F. Massey
Well Plugging Supervisor