

AFFIDAVIT AND COMPLETION FORM


ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR Phillips Petroleum Company API NO. 15-051-22,583-0088
 ADDRESS P.O. Box 287 COUNTY Ellis
Great Bend, Kansas 67530 FIELD Bemis-Shutts
 **CONTACT PERSON C. D. Dohrer LEASE York Hadley
 PHONE (316) 793-8421

PURCHASER None WELL NO. D02
 ADDRESS _____ WELL LOCATION 100' S of C NE NW SW
430 Ft. from South Line and
1650 Ft. from West Line of
 DRILLING CONTRACTOR Slawson Drilling Company the SW/4 SEC. 32 TWP. 11S RGE. 17W
 ADDRESS Great Bend, Kansas 67530

PLUGGING CONTRACTOR _____
 ADDRESS _____
 TOTAL DEPTH 3650' PBTD 1016'
 SPUD DATE 10-06-81 DATE COMPLETED 12-10-81
 ELEV: GR2052'DF KB 2058'



WELL PLAT
 (Quarter or Full) Section - Please indicate.
 Full Section ✓

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(AIR)~~ TOOLS
 Report of all strings set - surface, intermediate, production, etc. (New) / ~~(Used)~~ casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	307'	Common	225	2% gel, 3% CaCl & 1/4# Flocele/sk
Production	7 7/8"	5 1/2"	15.5#	1105'	Common	390	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4 HPF	4" Jumbo Jet	910-920', 870-880'

TUBING RECORD			STATE CORPORATION COMMISSION
Size	Setting depth	Packer set at	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD		DEC 14 1981
Amount and kind of material used		Depth interval treated
		CONSERVATION DIVISION Wichita, Kansas

TEST DATE: <u>12-09-81</u>		PRODUCTION	
Date of first production Disposal	Producing method (flowing, pumping, gas lift, etc.)	A.P.I. Gravity	
<u>12-09-81</u>		Gas-oil ratio	
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.
Disposition of gas (vented, used on lease or sold)		Producing interval (s) Disposal <u>870-880', 910-920'</u>	

** The person who can be reached by phone regarding any questions concerning this information.
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum _____ Depth 65'
 Estimated height of cement behind pipe surface

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface	0'	310'		
Shale	310'	1900'		
Shale	1900'	2738'		
Lime & Shale	2738'	3430'	Formation Tops:	
Shale & Lime	3430'	3604'	Anhydrite	1290'
Arbuckle	3604'	3650'	Topeka	3112'
			Toronto	3269'
			Lansing-KC	3292'
			Conglomerate	3568'
			Arbuckle	3604'
Total Depth	3650'			

WELL IS DISPOSING INTO THE CEDAR HILLS FORMATION.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T


STATE OF KANSAS, COUNTY OF BARTON SS,

C. D. DOHRER OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS AREA MANAGER FOR PHILLIPS PETROLEUM COMPANY OPERATOR OF THE YORK HADLEY LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. D02 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 10th DAY OF December 19 81; AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) C. D. Dohrer



SUBSCRIBED AND SWORN TO BEFORE ME THIS 11th DAY OF December 1981

Velma L. Mog
 NOTARY PUBLIC
 Velma L. Mog

MY COMMISSION EXPIRES: February 15, 1984