

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 7 TWP. 17S RGE. 25W E/W
Location as in quarters or footage from lines:
150' NW of SE SE NW

Lease Owner Chief Drilling Co., Inc.
 Lease Name STUTZ "D" Well No. 1
 Office Address 905 Century Plaza, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed 10-19-79
 Application for plugging filed 10-17-83
 Plugging commenced 11-16-83
 Plugging completed 11-16-83
 Reason for abandonment of well or producing formation
no longer producing

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacy
Producing formation Marmaton Depth to top 4202 bottom 4237 T.D. 4504'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	8 5/8"	28#	306'	common	3% c.c	2% gel, 180 sx. common
producing	4 1/2"	4482'	w/250 sx	60-40	posmix	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged w/85 sx. of 50-50 pos mix, 6% gel, down the casing
and 85 sx. down the annles, 5 sx. hulls. Started @ 10:00 a.m.
Finished @ 12:30 p.m.

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1983
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
F.W. Shelton, Jr., Vice Pres (employee of owner) ~~BY (OWNER OR OPERATOR)~~ of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.
F.W. Shelton, Jr., Vice Pres.
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1983



Martha E. Gustin
Martha E. Gustin Notary Public.

My Commission expires: _____

15-135-21704-00-00

WELL LOG

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 STUTZ "D"
150' NW of SE SE NW
Sec. 7-17S-25W
Ness County, Kansas
COMMENCED: Oct. 11, 1979
COMPLETED: Oct. 19, 1979

CONTRACTOR: Warrior Drilling, Inc.
CASING RECORD: 8 5/8" @ 306' w/180 sx.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Sand & Clay	0	310	2542 Gr.
Shale	310	2516	2544 D.F.
Shale & Lime	2516	3500	2547 K.B.
Lime & Shale	3500	4340	
Lime	4340	4504	
RTD	4504		

4 1/2" @ 4492' w/150 sx.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the 150' NW of SE SE NW of Section 7-17S-25W, Ness County, Kansas, to the best of my knowledge and belief.

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1983

CONSERVATION DIVISION
Wichita, Kansas

CHIEF DRILLING CO., INC.

Bill G. Lahar
Bill G. Lahar, Manager of Exploration

Subscribed and sworn to before me this 22nd day of October, 1979.

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS

Marilyn Sinard
Marilyn Sinard Notary Public

15-135-21704-00-00

WELL LOG

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 STUTZ "D"
150' NW of SE SE NW
Sec. 7-17S-25W
Ness County, Kansas
COMMENCED: Oct. 11, 1979
COMPLETED: Oct. 19, 1979

CONTRACTOR: Warrior Drilling, Inc.
CASING RECORD: 8 5/8" @ 306' w/180 sx.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Sand & Clay	0	310	2542 Gr.
Shale	310	2516	2544 D.F.
Shale & Lime	2516	3500	2547 K.B.
Lime & Shale	3500	4340	
Lime	4340	4504	
RTD	4504		

4 1/2" @ 4492' w/150 sx.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the 150' NW of SE SE NW of Section 7-17S-25W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC. OCT 23 1979

Bill G. Lahar
Bill G. Lahar, Manager of Exploration
CONSERVATION DIVISION
Wichita, Kansas
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this 22nd day of October, 1979

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY APPT. EXP. 4-30-83

Marilyn Sinard
Marilyn Sinard
Notary Public

KANSAS


WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 135 — 21,704 — 00-00
 County Number

S. 7 T. 17S R. 25W E W
 Loc. 150' NW of SE SE NW

County Ness

640 Acres
 N



Locate well correctly

Elev.: Gr. 2542

DF 2544 KB 2547

Operator
 Chief Drilling Co., Inc.

Address
 905 Century Plaza, Wichita, Kansas 67202

Well No. #1 Lease Name Stutz "D"

Footage Location:
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Geologist
 Warrior Drilling, Inc. Tom Wesselowski

Spud Date Date Completed Total Depth P.B.T.D.
 10/11/79 10/19/79 4504'

Directional Deviation Oil and/or Gas Purchaser
 Koch Oil Company

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	28 lb.	306'	Common	180	3% c.c., 2% gel.
		4 1/2"		4482'	60-40 Posmix	250	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type Reg.	Depth interval
			4		4257 1/2' to 4261'

Size	Setting depth	Packer set at
2 3/8"	4437'	4437'

RECEIVED
 STATE CORPORATION COMMISSION

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gals.	4257 1/2' to 4261'

INITIAL PRODUCTION

Date of first production 3-9-80 Producing method (flowing, pumping, gas lift, etc.) pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	100 bbls.	None MCF	2%	None CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s) 4202-37' (Marmaton)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Chief Drilling Co., Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name Stutz "D"	Oil Well
S <u>7</u> T <u>17S</u> R <u>25W</u> E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 4426-4500' 30-30 30-30 Wk. to inter. bl. 23 min. Rec. 10' Oil; 70' S10CM IBHP: 1205# FBHP: 1142# FP: 40-77#			Anhydrite Heebner Lansing BKC Ft. Scott Miss. Miss. Dolo. LTD RTD	1880 3825 3864 4176 4379 4473 4493 4504 4504

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p><i>Bill G. Lahar</i> Signature</p> <p>Bill G. Lahar, Vice President Title</p> <p>April 9, 1980 Date</p>
---------------	--