


15-135-21417-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Ness County, Sec. 7 Twp. 17S Rge. (E)25 (W)  
Location as "NE/CNWxSWx" or footage from lines C W/2 W/2 SW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name Stutz "B" Well No. #1  
Office Address 905 Century Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-23-78 19  
Application for plugging filed 2-27-78 19  
Application for plugging approved 2-23-78 19  
Plugging commenced 2-23-78 19  
Plugging completed 2-23-78 19  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4527' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	261'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged through drill pipe @ 720' w/70 sx. cement  
Plugged through drill pipe @ 240' w/20 sx. cement  
Plugged through drill pipe @ 40' w/10 sx. cement

RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1978

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.  
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jim Robinson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson  
905 Century Plaza, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of February, 1978

Marilyn Sinard  
Marilyn Sinard Notary Public.

My commission expires

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 30, 1979

15-135-~~20~~ 21417-00-00

WELL LOG

CHIEF DRILLING CO., INC.  
905 Century Plaza  
Wichita, Kansas 67202

#1 STUTZ "B"  
C W/2 W/2 SW Sec. 7-17S-25W  
Ness County, Kansas

CONTRACTOR: Warrior Drilling, Inc.  
CASING RECORD: 8 5/8" @ 261' w/170 sx.

COMMENCED: February 15, 1978  
COMPLETED: February 23, 1978

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Sand	0	265	2553 Gr.
Shale	265	1881	2556 D.F.
Anhydrite	1882	1917	2558 K.B.
Shale	1917	4407	
Lime & Shale	4407	4505	
Lime	4505	4508	
Shale	4508	4520	
Lime	4520	4527	
Total Depth	4527		

<u>FORMATION TOPS</u>	
Anhydrite	1885 + 673
Base Anhydrite	1916 + 642
Heebner	3830 - 1272
Lansing	3876 - 1318
BKC	4190 - 1632
Ft. Scott	4392 - 1834
Miss.	4488 - 1930
Miss. Dolo.	4494 - 1936
LTD	4527 - 1969
RTD	4527 - 1969

D & A

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1978  
CONSERVATION D.V.S.ON  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C W/2 W/2 SW/4 of Sec. 7-17S-25W Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson  
Jim Robinson, Vice-President

Subscribed and sworn to before me this 27th day of February, 1978.

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard  
Marilyn Sinard Notary Public