

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER #15-051-22310-0002

LEASE NAME Saline River Grazing  
Asso.

WELL NUMBER SRGA#1

3630 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 5 TWP. 11 RGE. 18 (E) or (W)

COUNTY Ellis

Date Well Completed 3/1/81

Plugging Commenced 3/13/00

Plugging Completed 3/13/00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kenny Brown Enterprises, LLC

ADDRESS P.O. Box 277 Hays, Ks. 67601-0277

PHONE # (785) 628-3384 OPERATORS LICENSE NO. 32250

Character of Well input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/13/00 (date)

by Herb Deines and Rich Williams (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached? yes

Producing Formation Kansas City Depth to Top 3435 Bottom 3523 T.O. 3557

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content surface	From top	To 171	Size 8 5/8	Put in 171,	Pulled out
	production	top	3557	4 1/2	3557	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from            feet to            feet each section. Hookup to 4 1/2 csg and pump 40 sacks SMD cement followed by 110 sacks SMD cement with 700 hulls max psi 400. Shut down well on slight vac. Hookup to 8 5/8 and pump 35 sacks SMD max PSI 250. Shut in 8 5/8 100 PSI. Hookup to 4 1/2 and pump 55 sacks to fill holding 200 PSI. Hookup to 8 5/8 and pump 10 sacks SMD.

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P.O. Box 466 Ness City, Ks. 785-798-2300 phone#

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kenny Brown Enterprises, LLC


STATE OF Kansas COUNTY OF Ellis, ss.

Stephen P. Ruder operator/member (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Stephen P Ruder

(Address) P.O. Box 277  
Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 14th day of March, 2000



Paul Gross  
Notary Public  
09/30/2002

STATE CORPORATION COMMISSION  
RECEIVED  
MAR 16 2000

USE ONLY ONE SIDE OF EACH FORM