

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-22537-0000

LEASE NAME Salina River Grazing Association

WELL NUMBER 7

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2870 Ft. from S. Section Line

2970 Ft. from E Section Line

SEC. 5 TWP. 11 RGE. 18 (E) or (W)

COUNTY Ellis

LEASE OPERATOR Kenny Brown Enterprises

ADDRESS Drawer 340 Plainville, Kansas

PHONE (913) 434-7236 OPERATORS LICENSE NO. 5537

Date Well Completed 8-3-81

Character of Well none producing

Plugging Commenced 9-4-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-4-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Lansing Kansas City Depth to Top 3455' Bottom 3542' T.D. 3580

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	surface			8 5/8"	174'	0
	long string			4 1/2"	3577'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged to abandon w/200 sacks 60-40- pos-mix, 6% gel 3% CC, 4 sacks of hulls and 9 sacks gel total. Pumped 70 sacks down annulus w/ 1 sack of hulls @ 500# pressure. Pumped 130 sacks w/ 3 sacks hulls 100# pressure down casing. solid plug. top to T.D.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address Hays, Kansas 67601

STATE OF Kansas COUNTY OF Rooks, ss.

Kenneth O Brown (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Kenneth O Brown

(Address) Plainville, Kansas 67663

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 1985

Barbara West RECEIVED

My Commission Expires: _____



STATE CORPORATION COMMISSION

SEP 9 1985

Form CP-4

Revised 08-84

CONSERVATION DIVISION

Hook up to annulas and pumped 50 sacks 60-40-pos mix, 6% gel, 3% C.C. w/ $\frac{1}{2}$ sack hulls
Hook up to 4 $\frac{1}{2}$ " casing and pumped 50 sacks cement w/ 3 sacks hulls, followed by 9 sks.
gel, and release plug and pumped 80 sacks cement, pressured to 500[#] psi and held 200[#]
psi. Closed in casing, hooked up to annulas and pumped 20 sacks w/ $\frac{1}{2}$ sack hulls,
pressured, to 300# and held 100 psi, closed annulas, job completed.

This well was squeezed 1-15-85 w/300sacks of Halliburton 60-40 pos-mix-between 924' to
957'.

