


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County, Sec. 5 Twp. 11 Rge. 18 (E) (W)  
Location as "NE/CNW\*SW\*" or footage from lines S 1/2 SE SW  
Lease Owner Leo J. Dreiling Oil Company  
Lease Name Richardson Well No. 1  
Office Address Victoria, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed Dec. 15, 1960 19  
Application for plugging filed Dec. 15, 1960 19  
Application for plugging approved Dec. 15, 1960 19  
Plugging commenced Dec. 15, 1960 19  
Plugging completed Dec. 15, 1960 19  
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3640' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	165'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Rotary mud was used to fill up hole to a depth of 540' where 1st plug was set using 20 sacks cement, 2nd plug was set at 160' using rotary mud and used 20 sacks cement, 3rd plug was set at 40' using 10 sacks cement and filling hole to top.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. DREILING AND SONS, INC.  
Address VICTORIA, KANSAS


STATE OF KANSAS, COUNTY OF ELLIS, ss.  
I, Leo F. Dreiling a partner (Name of Operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 1962

My commission expires August 31, 1965

Renan Zimmerman  
Notary Public.



LEO J. DREILING AND SONS, INC.  
VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Victoria, Kansas	Sec. 5	Twp. 11	Rng. 18
Farm	Richardson No. # 1	Location	S2 SE SW	
Total Depth	3640'	County	Ellis County, Kansas	
Comm.	12-6-60	Comp.	12-15-60	Elevation: D. F. 2037
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas			G. R. 2034
	Casing Record	Cement Record		Production:
	8 5/8 - - - 165'	130 SAGS CEMENT		D & A

Figures Indicate Bottom of Formations

0 - 40	SURFACE CLAY & SHELL ROCK
40 - 164	SHALE & SHELLS
164 - 310	SHALE
310 - 615	SAND & SHALE
615 - 895	SANDY SHALE & SHELLS
895 - 1065	SAND
1065 - 1325	RED ROCK & SHALE
1325 - 1381	SHALE
1381 - 1422	ANHYDRITE
1422 - 1640	SHALE
1640 - 1885	SHALE & SHELLS
1885 - 2050	SHALE & BROKEN LIME
2050 - 2233	SHALE & LIME
2233 - 2325	LIME & SHALE
2325 - 2465	LIME & SHALE
2465 - 2575	LIME & SHALE
2575 - 2700	LIME & SHALE
2700 - 2830	SHALE & LIME
2830 - 2935	SHALE & LIME
2935 - 2990	LIME
2990 - 3125	LIME & SHALE
3125 - 3200	LIME & SHALE
3200 - 3263	LIME
3263 - 3320	LIME
3320 - 3361	LIME
3361 - 3413	LIME
3413 - 3460	LIME
3460 - 3502	LIME
3502 - 3548	LIME
3548 - 3607	LIME & CHERT
3607 - 3640	CHERT, LIME & CONGLOMERATE
3640	TD

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 2 1962  
CONSERVATION DIVISION

STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo J. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Richardson # 1.

*Leo J. Dreiling*  
\_\_\_\_\_  
LEO J. DREILING

Subscribed and sworn to before me this 22th day of May, 1961.

*Ronald Zimmerman*  
\_\_\_\_\_  
NOTARY PUBLIC

My Commission Expires: August 14, 1965

