

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-22.852-00-00

LEASE NAME Fuller

WELL NUMBER #1

3415' FSL

SPOT LOCATION 3090' FEL

SEC. 4 TWP. 17 RGE 25 (E) or (W)

COUNTY Ness

Date Well Completed 7-8-85

Plugging Commenced 11:00 A.M.

Plugging Completed 4:00 P.M.
7-8-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Dreiling Ltd. of Colorado

ADDRESS 410 - 17th St., Suite 1140, Denver, Co. 80202

PHONE # (303) 623-6144 OPERATORS LICENSE NO. 5804

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation None Depth to top _____ bottom T.D. 4494

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippian	93' free oil.					
	31' OCM	4472	4487	8-5/8	366	None
MISSISSIPPIAN	62' free oil.					
	62' OCM	4477	4494			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hole full of heavy mud, pumped cement through drill pipe as follows: 1st cement plug at 1890' with 50 sacks, 2nd cement plug at 1050' with 80 sacks, 3rd cement plug at 390' with 40 sacks, 4th cement plug at 40' with 10 sacks, 5 sacks in rathole, 10 sacks in mousehole. 205 sacks total. 60-40 pozmix 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Ness City, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

LES OLSON

(employee of operator) or

~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Les Olson*

(Address) 410 - 17th St., Suite 1140
 Denver, Colorado 80202

SUBSCRIBED AND SWORN TO before me this 17 day of July, 1985

Lorraine C. Murphy
 Notary Public



My Commission expires: 9-2-87

RECEIVED
 STATE CORPORATION COMMISSION

7.19.85
JUL 19 9:00

Form CP-4 1-84
 Revised 06-83