


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-135-00030-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 3 Twp. 17 Rge. 25 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner F. Kirk Johnson
Lease Name Moellenkamp Well No. 1
Office Address 3101 Winthrop, Ft. Worth, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 11/26 19 54
Application for plugging filed 11/25 verbally 19 54
Application for plugging approved 11/26 verbally 19 54
Plugging commenced 11/26 19 54
Plugging completed 11/26 19 54
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4695 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	288 1/2'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 275'. Pushed plug down, cement through drill pipe with 1/2 sack hulls & 20 sacks cement. Filled hole to 35' with heavy mud. Pushed plug to 35'. Cemented with 1/4 sack hulls & 10 sacks cement.

12-3-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bennett & Roberts Drilling Co.
Address Russell, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
BENNETT & ROBERTS DRILLING CO.
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 19 54

Clara Hummel
Notary Public.

6/17/58

Notary Public.

PLUGGING
FILED SEC 3 TWP 17 R 25 W
BOOK PAGE 20 LINE 43

15-135-00030-00-00

F. Kirk Johnson
Moellenkamp #1

NW NW NW Sec. 3-17-25
Ness County, Kansas

Contractor - Bennett & Roberts Drilling Co.

R.T.D. 4695

Comm: 11/5/54
Comp: 11/26/54

Casing
8 5/8" Set @ 288 1/2'

Cement
185 sx

Formation:	Depth:
Top soil & Clay	60'
Sand	90
Blue & white shale	195
Gray shale & Shells	289
Gray shale & shells	400
Sandy shale	420
Shale	650
Sand	750
Shale, shells & sand	860
Green & blue shale	1150
Red Bed & Shale	1250
Red bed	1260
Anhydrite	1287
Red bed	1305
Sand & shale	1600
Shale & Shells	1880
Lime	1915
Shale & Shells	2545
Shale & Lime	2600
Lime	3175
Lime & Shale	3594
Lime	3698
Lime & Shale	3782
Lime	3956
Lime & Stks of chert	3986
Lime	4358
Lime & Shale	4387
Shale	4398
Lime	4474
Lime & stks of chert	4506
Lime & Chert	4522
Lime	4595
Lime, Chert	4609
Lime	4616
Lime, Cherty	4643
Lime & Chert	4692
Chert	4695

STATE OF KANSAS
COUNTY OF RUSSELL

I hereby certify that the above information is correct to the best
of my knowledge.

BENNETT & ROBERTS DRILLING CO.

By Quin Lake

Subscribed and sworn to before me this 1st day of December, 1954.

Charles Hummel
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE SEC 3-17-25
BOOK PAGE 80 LINE 43