

15-135-20823-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness County, Sec. 2 Twp. 17S Rge. (E) 25 (W)
Location as "NE/CNW/SE/SW" or footage from lines C/NE NE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Breit Well No. 1
Office Address 4328 East Kellogg, P. O. Box 18407, Wichita, Kansas 67218
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 4 19 74
Application for plugging filed January 4 19 74
Application for plugging approved January 4 19 74
Plugging commenced January 4 19 74
Plugging completed January 4 19 74
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays
Producing formation Depth to top Bottom Total Depth of Well 4510 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	284'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Hole plugged as follows: Plugged at 750' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 10:30 P. M. January 4, 1974.

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1974


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 1974.
My commission expires December 14, 1977



Elaine H. Taylor
Notary Public.

DRILLERS LOG

#1 Breit

CASING RECORD:
279.76' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling Inc.

DESCRIPTION: C/NE NE
Section 2-17S-25W
Ness County, Kansas

TOTAL DEPTH:
4510'

COMMENCED: December 21, 1973
COMPLETED: January 5 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale w/Sand Streaks	0	130	Ran 279.76' of used 8-5/8" surface casing; set and cemented at 284' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 4:00 A. M December 22, 1973.
Shale	130	1200	
Shale w/Lime Streaks	1200	2475	
Lime & Shale	2475	4260	
Lime	4260	4350	
Lime & Shale	4350	4435	
Dolomite	4435	4455	
Lime	4455	4510	

ROTARY TOTAL DEPTH: 4510'

Ran electric log.

D. & A.

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1974
CONSERVATION DIVISION
Wichita, Kansas

Plugged hole as follows: Plugged at 750' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 240' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 10:30 P. M. January 4, 1974.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 8th day of January, 1974.

My Commission Expires:

December 14, 1977

Elaine H Taylor
Elaine H Taylor, Notary Public

