

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3988
Name: Slawson Exploration Company Inc.
Address 1: 204 N Robinson Ave STE 2300
Address 2: _____
City: Oklahoma City State: OK Zip: 73102 +6891
Contact Person: Steve Slawson
Phone: (405) 232-0201
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
St Louis Depth to Top: 6493' Bottom: 6500' T.D. _____
Cherokee Depth to Top: 6135' Bottom: 6148' T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15- 175-21144-00-00
Spot Description: _____
E 1/4 NE Sec. 14 Twp. 34 S. R. 34 East West
3300 3306 Feet from North / South Line of Section
1650 1665 Feet from East / West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Seward
Lease Name: Stephens Well #: 1-14
Date Well Completed: _____
The plugging proposal was approved on: 4-18-12 (Date)
by: Eric McLeandyn (KCC District Agent's Name)
Plugging Commenced: 4-20-12
Plugging Completed: 4-23-12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Puffed Out
		Conductor	20"	54'	-0-
		Surface	8 5/8"	11658'	-0-
		Production	4 1/2"	6595'	2500'

RECEIVED
MAY 07 2012
5-7-12
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 20 sks cut. 200# hulls displ. w/mud to 5800' (5800'-6148'). Shot + pulled 4 1/2 @ 2500' placed plugs as follows: 50 sks cut. 1680'-1515'; 40 sks cut 650'-515' 10 sks cut. 40'-0'. With mud spacing each plug. Cut + Cap 8 3/8 4' below GL.

Plugging Contractor License #: 32833 Name: Sargent + Lillard Casing Pulling Inc.
Address 1: P.O. Box 1450 Address 2: _____
City: Woodward State: OK Zip: 73802 +1450
Phone: (580) 254-1881
Name of Party Responsible for Plugging Fees: Slawson Exploration Co, Inc
State of Oklahoma County, Oklahoma ss. _____
Stephen B Slawson Employee of Operator or Operator on above-described well.
(Print Name)
being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: _____

AK