

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21739-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 7-11S-21W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: RUNNING W GRAZING Well #: 1-W  
County: TREGO Total Vertical Depth: 3852 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		
PROD	4.5	3850		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2012 12:00 PM  
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC  
Proposal Rcvd. from: JOE Company: OUTLAW WELL SERVICE LLC Phone: \_\_\_\_\_

Proposed Plugging Method: Ordered 285 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack. 600 # HULLS AND 10 SXS GEL SHOOT PERFS @ 2175', 1800', 990', 270'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/05/2012 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

RUN TUBING TO 3774' PUMP 10 SXS GEL FOLLOWED WITH 50 SXS CEMENT. PULL TUBING TO 2200' PUMP 90 SXS CEMENT WITH 200# HULLS. PULL TUBING TO 1100' PUMP 95 SXS CEMENT WITH 100 # HULLS. PULL TUBING OUT TIE ON CASING PUMP 20 SXS CEMENT SHUT IN 400 PSI. TIE ON BACK SIDE FULL 850 PSI.

RECEIVED  
APR 13 2012  
KCC WICHITA

Remarks: CONTROL #20100032-001 FEE FUND PROJECT RUNNING SOS CEMENT CO. TK # 562  
NAD 83 39.10590 99.70213 GPS Date 3-27-2009 GPS By Marvin Mills  
Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

APR 06 2012