

District Plugging Report

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>COND - Conductor Pipe</u>	<u>10.000</u>	<u>20</u>	<u>0</u>	<u>EST ON SURFACE</u>
Address 1: <u>130 S. MARKET</u>					
Address 2: _____					
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 5/9/11 / 9:00 am
 Plug Co License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
 Proposal Rcvd from: KEITH SPLANE Company Name: SAME Phone: (620) 431-1359

Proposed Plugging Report:

FILL WELL WITH PORTLAND CEMENT FROM TD TO SURFACE.

KANSAS CORPORATION COMMISSION

MAY 20 2011

RECEIVED

Plugging Proposal Received By: FRANK GUILFOYLE **Witness Type:** COMP - Complete 100%
Date/Time Plugging Completed: 5/9/11 / 12:30 pm **KCC Agent:** FRANK GUILFOYLE
Actual Plugging Report: **Perfs:** **Top** **Bottom** **Thru**

CLEAR TREES FROM LOCATION. REMOVE OLD PUMP JACK. DIG DOWN AND CUT OFF SURFACE. SET SURFACE. DELIVER AND SPREAD ROCK. DRILL DOWN THROUGH CEMENT, WOOD, AND CUTTINGS. DRILL TO 400 FT AND HIT GOOD CEMENT. PULL DRILL STEEL AND RUN 1" TO 400 FT. PUMP PORTLAND CEMENT TO SURFACE AND PULL PIPE. TOP OFF WELL. PUMP TOTAL OF 191 SACKS OF CEMENT. EMPTY PIT. DIG OUT SURFACE AND CUT OFF. FILL PIT AND LEVEL OUT AREA.

[illegible]

Remarks	Control # 20110040-014. GPS date-12-28-2010. 38.00625, -95.56064. PO # 14300-0000000415. Reg Sect.
---------	--

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☒ Yes ☐ No**District: 03**

Frank Smith
(Technician)

Form: District Plugging Report -