

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-06487-00-00  
Spot: SESESW Sec/Twnshp/Rge: 25-13S-15W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SELLENS Well #: 3  
County: RUSSELL Total Vertical Depth: 3337 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	231		
PROD	5	3335		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/29/2012 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: \_\_\_\_\_

Proposed Plugging Method: Ordered 330sx 60/40 4% gel cement and 400# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/29/2012 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Hit bridges @140', 600', 2075'. Worked through to 2790'.  
Ran tubing to 2790'. Pumped 100sx cmt w/100# hulls.  
Pulled tubing to 1660'. Perforated through bottom jt.  
Pumped 90sx cmt w/150# hulls.  
Pulled to 450'. Perforated through bottom jt.  
PTOH. Perforated @200'.  
Ran tubing to 700'. Circulated w/90sx cmt w/150# hulls.  
Pumped 40sx cmt down backside.  
Topped off w/10sx cmt.

Remarks: CONTROL #20120017-002 FEE FUND PROJECT SELLENS II

Plugged through: TBG

District: 04 Signed Case Morris  
(TECHNICIAN)

MAR 13 2012

RECEIVED  
MAR 20 2012  
KCC WICHITA  
Form CP-2/3