

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21557-00-00  
Spot: N2SWSWNE Sec/Twnshp/Rge: 36-16S-20W  
3143 feet from S Section Line, 2322 feet from E Section Line  
Lease Name: BALDWIN Well #: 1-2936  
County: RUSH Total Vertical Depth: 3867 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	275		WITH 275 SX CMT
DVT		1382		WITH 225 SX CMT
PROD	5.5	3840	0	WITH 325 SX CMT

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/09/2012 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: RUN TBG TO 3800' & MIX 15 SX GEL & 200# HULLS, THEN 50 SX CMT. PULL TBG TO 1400' & CIRCULATED CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/09/2012 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG RUN TBG TO 3286' & MIX 14 SX GEL & 200# HULLS, THEN 50 SX CMT.  
2ND PLUG PULL TBG TO 1396' & PUMP 160 SX CMT. CIRCULATED TO SURFACE.  
3RD PLUG PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE  
& PUMPED 100 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
3840	3867	OH	

Remarks: CONTROL # 20120036-001. USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED  
MAR 22 2012  
KCC DODGE CITY

Signed

Michael J. Maier  
(TECHNICIAN)

RECEIVED  
MAR 28 2012  
KCC WICHITA