

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21,265-0001

LEASE NAME School

WELL NUMBER 1

COPY

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line E2SWSW

4300 Ft. from E Section Line

Sec 16 TWP. 25 RGE. 9W (E) or (W)

FILE 2 COUNTY Reno

LEASE OPERATOR Mach Petroleum, Inc.

ADDRESS P. O. Box 35583 Tulsa, OK 74156-5583

PHONE# (918) 496-0442 OPERATORS LICENSE NO. 30146

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 7-25-94

Plugging Completed 7-26-94

The plugging proposal was approved on _____ (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4007'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	200'	none
				5 1/2	4007'	2960'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each set. Shot well @ 2960', pipe came loose. Pulled up to 1400', pumped 35 sks cement. Pulled to 825' pumped 35 sks cement. Pulled to 250', circulated 85 sks cement to surface. Pulled rest of pipe, topped off with 10 sks cement. 60/40 poz 4% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mach Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 28th day of July, 19 94

My Commission Expires: _____



Notary Public

Form CP-1
Revised 05-08

2K