

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3911
Name: Rama Operating Co., Inc.
Address 1: 101 S Main St
Address 2: _____
City: Stafford State: KS Zip: 67578 + 1429
Contact Person: Robin Austin
Phone: (620) 234-5191
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 151-10800-00-00
Spot Description: _____
SE SE SE Sec. 29 Twp. 26 S. R. 13 East West
~~330~~ 324 Feet from North / South Line of Section
~~330~~ 339 Feet from East / West Line of Section
GPS - KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Pratt
Lease Name: Mowbray Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Steve Peifer (KCC District Agent's Name)
Plugging Commenced: 2/28/12
Plugging Completed: 3/17/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			10 3/4 "	850'	None
			7 "	4251'	1202'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rigged up LogTech, perf hole @ 2559'. Ran in 2600' of 2-3/8 rental. Rigged up Copeland, pumped 10sx gel & 100sx 60/40poz. Displaced to bottom. Pulled out tubing. Ran bailer, tagged top cement @ 2050'. Cut casing head off, cut casing loose @ 1202'. Laid down 7". Ran in 2-3/8 tubing to 880'. Pumped 20sx gel with 75sx 60/40poz. Pulled to 415', pumped 75sx 60/40poz. Pulled to 60', pumped 40sx 60/40poz. Cement circulated to surface. Pulled rest of tubing.

Plugging Contractor License #: 31529 Name: Mike's Testing and Salvage, Inc.
Address 1: PO Box 467 Address 2: _____
City: Chase State: KS Zip: 67524 + _____
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: Rama Operating Co., Inc.
State of KS County, Rice, ss. _____
Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso

RECEIVED
MAY 10 2012