

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32628  
Name: Quantum Operating Company  
Address 1: PO Box 3029  
Address 2: \_\_\_\_\_  
City: Denver State: CO Zip: 80201 + \_\_\_\_\_  
Contact Person: Eugene Nichols  
Phone: ( 720 ) 488-4942  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 187-20399 · 00 · 00  
Spot Description: NE NE 4725 North, 785 West from SE Corner  
NE NE Sec. 25 Twp. 30 S. R. 42  East  West  
555 4725 Feet from  North /  South Line of Section  
765 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Stanton  
Lease Name: Baughman Well #: 1-25  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: 8/16/11 (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Plugging Commenced: 1/13/12  
Plugging Completed: 1/19/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	1505'	725 Sacks Cement
		Production	4 1/2"	5637'	565 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole, sand at 5042'; bailed 4 sacks cement on sand. Slips stuck, no stretch, cut casing head apart. Had Log-tech do bond log. Had cement from 82' to 1910'. Changed over for tubing, ran tubing to 1600' & pumped 7 gel, 110 sacks cement, 200# hulls, 60/40 4%. Cement circulated, pulled tubing out. Pumped 50 sacks cement. Cement was falling back; shut down. Ran tubing to 512' & pumped 40 sacks cement. Well circulated. Pulled tubing out. Topped off with 10 sacks cement. Cut 4-1/2" casing off 4' below ground.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc  
Address 1: 190 US Hwy 56 Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526  
Phone: ( 620 ) 727-3409

Name of Party Responsible for Plugging Fees: Quantum Operating Company

State of Colorado County, Arapahoe, ss.

Quantum Operating Corp (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: \_\_\_\_\_

RECEIVED  
MAY 10 2012  
KCC WICHITA

SR