

WELL PLUGGING RECORD

15-051-30256-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Ellis County, Sec. 6 Twp. 13 Rge. 17 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines C-W 1/2 NE-SU

Lease Owner Leo J. Dreiling Oil Company

Lease Name Staab A Well No. #4

Office Address Victoria, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 2-12-19 66

Application for plugging filed 2-12-19 66

Application for plugging approved 2-12-19 66

Plugging commenced 2-12-19 66

Plugging completed 2-12-19 66

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gib Leiker-Victoria, Kansas

Producing formation Depth to top -0- Bottom -0- Total Depth of Well 3629 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8-5/8"	145'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud to a depth of 540' where 1st plug was set using 20 sacks cement. Filling hole with rotary mud to a depth of 140' where 2nd plug was set using 20 sks. cmt. Rotary mud was used to fill hole to a depth of 40' where 3rd plug was set using 10 sks cement and filling hole to surface.

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1966
2-18-66
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L.J. Dreiling & Sons, Inc.

Address Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.

I, Leo F. Dreiling, a partner (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

Leo F. Dreiling Victoria, Kansas

(Address)


SUBSCRIBED AND SWORN to before me this 15th day of February, 1966

Elmer Weltz

Elmer Weltz

Notary Public.

My commission expires October 26, 1968



L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

15-051-30256-0000

WELL LOG

Company	Leo J. Dreiling Oil Co. Victoria, Kansas	Sec. 6-	Twp. 13	Rng. 17
Farm	Staab "A" No. 7 # 4	Location	C-W/2 NE SW	
Total Depth	3629'	County	Ellis	
Comm.	2-7-66 Comp. 2-12-66	Elevation:	D. F. 2063 K. B. 2066 G. R. 2061	
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas	Production:	D & A	
	Casing Record Cement Record			
	145' 8-5/8" 100 sax			

Figures Indicate Bottom of Formations

0'	10'	Clay & Soil
10'	50'	Gravel & Sand
50'	80'	Clay & Shale
80'	145'	Shale
145'	762'	Shale & Sand Strks
762'	945'	Sand
945'	1285'	Redbed & Shale
1285'	1300'	Anhy
1300'	1326'	Anhy.
1326'	1696'	Shale & Redbed
1696'	1810'	Shale & Salt
1810'	1925'	Shale
1925'	2255'	Shale & Lime
2255'	2465'	Shale & Lime
2465'	2700'	Shale & Lime
2700'	3035'	Shale & Lime
3035'	3190'	Everett L. Mickelson
3190'	3307'	Lime
3307'	3389'	Lime
3389'	3500'	Lime
3500'	3597'	Lime
3597'	3629'	T.D.

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling report from your Staab A # 4.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 15th day of February, 1966

Elmer Heltz

NOTARY PUBLIC

My commission expires: October 26, 1968

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1966