

KCC OIL/GAS REGULATORY OFFICE

15-171-20059-00-01

ALT2

DATE (4-6-98) (4-7-98)

- New Situation
- Response to Request
- Follow-up

OPERATOR Berexco Inc. # 5363

NAME 970 Fourth Finance

LOCATION Sw, SEC 17, T 17 S, R 31 E W

ADDRESS Wichita KS 67202

LEASE Brookover Unit Well # 8-17

PHONE NO. OPER. 916-265-3311 OTHER _____

COUNTY Scott

REASON FOR INVESTIGATION: ALT II for Enhanced Recovery (Flood)
D# E-27, 364

LEASE INSPECTION

PROBLEM: _____

PERSON(S) CONTACTED: _____

(Ted Crawford Prod. Forman over seeing job.)

FINDINGS: Perforated by Perf Tech @ 1250', Allied ran Ins rate
1300# Max @ 1/2 bbl per min, broke down after 4 bbl in
pumping. @ 3 bbl per min @ 500#, waited on gel to pump
ahead of cement, Allied pumped 25 sx gel + 200 sx
60/40 2% gel + 2% CC. Max PSI ⁷⁰⁰ ~~1200~~ shut in @
800#.

COMPLAINT

Bob Grant Prod. Forman

(4-7-98) Perf-Tech ran Temp. surv. Found top cement @
1160' perf @ 850', ran Tubing & Packer to 720'. Allied ran Ins rate
@ 3 bbl per min @ 600#, Allied pumped 17 sx gel + 200 sx 60/40 6% 2% CC
+ 300# shut in 200# let set + squeezed.

photos taken: _____

ACTION/RECOMMENDATIONS: _____

FIELD REPORT

RECEIVED
KANSAS CORPORATION COMMISSION

APR 13 1998

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

CONSERVATION DIVISION
WICHITA, KS

By Kevin D Stube
PIRT II