

KCC OIL/GAS REGULATORY OFFICE

ALTZ

DATE 9/23/93

- New Situation
- Response to Request
- Follow-up

OPERATOR Robert F. Hembree # 8247

NAME P.O. Box 458

LOCATION SW SW NE, SEC 8, T 17 S, R 21 W

& ADDRESS Ness City, KS 67560-4058

LEASE Ryan A Well # 1-8

PHONE NO. _____
OPER. _____ OTHER _____

COUNTY Ness API# 15-135-23,619 0000

REASON FOR INVESTIGATION: Witness Alternate II cementing

PROBLEM: _____

LEASE INSPECTION

PERSON(S) CONTACTED: Robert F. Hembree

FINDINGS: 8 5/8" surface casing at 334' w/180 sx cement

Port collar at 1618', Anhydrite 1526-60' from Geologist's log

Set plug and sand at 2100', opened port collar and pumped in 20 bbl. gel slurry and

250 sx 60/40 Pozmix 8% gel, cement did circulate.

COMPLAINT

ACTION/RECOMMENDATIONS: _____ photos taken: _____

FIELD REPORT

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Duane Rankin

9/24/93